

Ocean

Complex Lifting Operations:

Rigid Spool Bundles Installation for Johan Castberg Project

Amund Helvik

Senior Installation Engineer

Subsea Expo 2024, February 21st, Aberdeen

Installer

Ocean Installer at a glance

A marine construction company focusing on SURF, mooring, renewables and carbon capture



Reputable offshore installation company with a solid track record in subsea and marine operations



Established in 2011 by HitecVision (100% ownership)



Headquartered in Stavanger, Norway, with offices in Oslo, Houston, Aberdeen & Dubai




Approx. 270 employees, 50% Technical and Operations



Experienced in full EPCI and complex logistical challenges, with strong safety culture and track record



Contract backlog of firm NOK 5,2 + 6bn in partnership agreements (Q2-2023)



- 1 Project & Spool Installation Scope Briefing
- 2 Spreader Bar and Rigging Design
- 3 Lifting Operations and Subsea Landing
- 4 Advantages and Challenges Associated with Spool Bundle Lift
- 5 Simulations Training and Comparison with Reality

Rigid Spool Bundles Installation for Johan Castberg Project

Project Summary

Johan Castberg Project

>850000 man hours at July 2022

0 Lost time injuries 0 Restricted work-day cases

15 mooring piles
1591Te

15 mooring lines
7750Te/15000m

22 risers anchors
1155Te

2 dynamic umbilicals
8556m

9 risers

19 spools

2 inline tees
26Te

10 manifolds
1300Te

6 static flowlines
21199m

12 static umbilicals
37911m

2 satellite structures
212Te

10 template structures
2663Te

Johan Castberg Field
Barents Sea
240km from Hammerfest, Norway

EC 2-off 10" Spools
EB 3-off 10" Spools
EA 3-off 10" Spools


CA 3-off 10" Spools
CB - 3-off 10" Spools
DA 1-off 10" Spool

CD - 2-off 6" Spools
CC - 2-off 10" Spools

Total 19-off rigid spools
 1-off single spool
 3-off 2-spools bundles
 4-off 3-spools bundles
 Water Depth: 340 - 405m

Rigid Spool Bundles Installation for Johan Castberg Project


Typical Spools Configuration Subsea



Rigid Spool Bundles Installation for Johan Castberg Project

Mobilisation base: Polarbase in Hammerfest

- Main onshore base for the entire project
- Fabrication of the 19-off rigid spools including field joint coating and testing
- Storage of project equipment including rigging and installation aids
- Preparation of the spools into bundle configuration including onshore test lift and transport of bundle assemblies to quayside
- Load out of spool bundles onto installation vessel



Installation Vessel:


Viking Neptun, state-of-the-art DP3, heavy construction vessel with high capabilities for heavy lifting (400Te main crane AHC, 2x WROVs)

- 1 Project & Spool Installation Scope Briefing
- 2 Spreader Bar and Rigging Design
- 3 Lifting Operations and Subsea Landing
- 4 Advantages and Challenges Associated with Spool Bundle Lift
- 5 Simulations Training and Comparison with Reality

Rigid Spool Bundles Installation for Johan Castberg Project

Spreader Bar Design and Modularity

- Spool – Very delicate and sensitive piece of equipment
- Installed between 2 preinstalled mating structures
- Designed in 2 phases – Pre-metrology and Post-metrology
- Need very good planning & engineering for installation
- One of most important aspect – Spreader bar design
- Modular design adopted (Parts connected with bolted flange connection)
 - Possibility to recover in parts – If recovery as whole difficult due to weather condition
 - Reusability of parts - 4 modular sets used for 7 lifts
 - More than 120Te of steel saved
 - Easier transport and storage
 - Flexibility in selection of fabricator (cost efficiency)




- BLUE - RE-USABLE SUB-ASSEMBLY, PRE-METROLOGY FABRICATION. SEE DRAWINGS FROM NO-1069-28500-N-XG-0101 TO 0107 FOR TOTAL QUANTITIES
- GREEN - NON RE-USEABLE/ SPECIFIC SUB-ASSEMBLY, PRE-METROLOGY FABRICATION.
- RED - POST-METROLOGY FABRICATION (CUTTING & WELDING).

Rigid Spool Bundles Installation for Johan Castberg Project

Innovative Technique : Spreader Bar Ballast System

- One of most important aspect of lift design – Adjust CoG Spreader Bar over CoG of Spool
 - Flat / horizontal Lift
 - Stability of spreader after spool landing
- Solution: adjust and try to match CoG of empty spreader bar with CoG of complete assembly by adding a ballast system onto the spreader bar
- Invented a CoG Adjustment System with Pinned Lever Beam
- Main Advantages:
 - Managed to bring down ballast weight within crane capacity
 - Ballast weight directly on crane. No significant effect on spreader bar integrity
 - Pinned connection – easy to adjust angle post-metrology




Rigid Spool Bundles Installation for Johan Castberg Project

Spreader Bar Ballast System



Rigid Spool Bundles Installation for Johan Castberg Project


Lift Rigging Details



Rigid Spool Bundles Installation for Johan Castberg Project

Lift Rigging Details

Bottom Rigging



Rigid Spool Bundles Installation

- 1 Project & Spool Installation Scope Briefing
- 2 Spreader Bar and Rigging Design
- 3 Lifting Operations and Subsea Landing
- 4 Advantages and Challenges Associated with Spool Bundle Lift
- 5 Simulations Training and Comparison with Reality

Rigid Spool Bundles Installation for Johan Castberg Project

Loadout Operations at Polarbase

- All spool bundles loadout performed at Polarbase quay 4 using Viking Neptun main crane.
- Bundle lifted with all supports (spools and spreader bar) pre-attached
- For the largest bundles, an overhanging platform and support required to 'extend' the vessel deck on starboard side.
- Bundle total weight range: **92Te to 174Te**
- Seafastening of bundle on deck made of chains and cargo straps connected to D-rings welded to deck.



Rigid Spool Bundles Installation for Johan Castberg Project

Offshore Lifting Operations


- Full dynamic analysis performed with Orcaflex software for all critical steps including the lift through the splash zone.
- Analysis results provided maximum design sea states for each lift depending on the wave period of the day.
- Limiting factor is actually the movement of the load on deck at the start of the lift.
- Alpha factors (defined by DNV) considered for weather forecast inaccuracy.
- Use of crane tuggers and rigger's slip lines only.
- Crane radius had to be increased during the lift due to size of the bundle.
- Multiple watchers on deck communicating with the deck foreman (banksman) to inform when to start slewing the crane and to warn for potential contact or entanglement.



Rigid Spool Bundles Installation for Johan Castberg Project

Subsea Landing Operations

- Disconnection and removal of PLR (Pig Launcher and Receiver)
- Installation of long guideposts onto porch receptacles, 2 different heights
- Spool bundle lowered through the water column
- ROVs are monitoring each end of the bundle (ILS ends and Template ends)
- Several ROV relocation required – slow but controlled operation



Rigid Spool Bundles Installation for Johan Castberg Project

Subsea Landing Operations

- Positioning spool termination heads above guideposts
- Spools engaged into all three guideposts
- ROVs guiding spools onto ILS guide rails
- All spool termination heads (up to 6) landing on porches at the same time
- Once full and correct landing confirmed, bottom rigging slacked and started rigging disconnection by ROVs
- Recovery of empty spreader bar to deck



Rigid Spool Bundles Installation

- 1 Project & Spool Installation Scope Briefing
- 2 Spreader Bar and Rigging Design
- 3 Lifting Operations and Subsea Landing
- 4 Advantages and Challenges Associated with Spool Bundle Lift
- 5 Simulations Training and Comparison with Reality

Rigid Spool Bundles Installation for Johan Castberg Project

Advantages and Challenges Associated with Spool Bundle Lift

Main Advantages:

- 19 single spools VS 8 spool bundles
- Fewer lifts (loadout and over boarding offshore with high risk)
- Shorter offshore campaign, less vessel transits and mobilisations
- Reduced time subsea on each site (efficiency and flexibility in the overall offshore schedule)
- Reduced risk of clash between spools or other subsea structures
- Better re-use philosophy for spreader frame compared to single spool lift with specific bracings
- Deck space requirement marginally equal between single or bundle solution




Rigid Spool Bundles Installation for Johan Castberg Project

Advantages and Challenges Associated with Spool Bundle Lift

Main Challenges:

- Harsh environment in Hammerfest (start of onshore preparation in February to be ready in May)
- Large amount of rigging to be managed – remote location no rigging should be missed/forgotten
- Very large bundle (footprint and height)
 - Deck space
 - Sufficient storage area on the base
 - Additional crawler crane mobilized in Polarbase
- Accurate positioning (dim control) of spools within the bundle to make sure landing is possible





Rigid Spool Bundles Installation

- 1 Project & Spool Installation Scope Briefing
- 2 Spreader Bar and Rigging Design
- 3 Lifting Operations and Subsea Landing
- 4 Advantages and Challenges Associated with Spool Bundle Lift
- 5 Simulations Training and Comparison with Reality

Rigid Spool Bundles Installation for Johan Castberg Project


Simulations Training at OSC

- Spool bundle installation simulations that were performed at OSC in Ålesund, Norway.
- The simulator consists of real-life environments of the vessel bridge, main control desk, 2-off ROVs, crane driver, and deck team stations that are linked together in a virtual world.
- Installation vessel model was prepared for the full operation, including 2 off deck winches. The crane was fully modelled including crane tugger winches.
- The installation vessel model hydrodynamic properties respond realistically to waves, winds and currents in the virtual environment.




Rigid Spool Bundles Installation for Johan Castberg Project

Video 1: Overboarding: Comparison between Simulation and Reality



Rigid Spool Bundles Installation for Johan Castberg Project

Video 2: Subsea Landing Simulation



Ocean

A photograph of an offshore oil rig installation. In the foreground, a worker wearing a red jacket with "OceanInstaller" on the back and a white hard hat is seen from behind, looking out at the sea. In the background, a large, dark, cylindrical structure, likely a wellhead or riser, is being lowered into the water by a crane. The structure is suspended by orange and blue cables. The sea is a dark blue-grey color, and the sky is overcast.

Thank you

Amund Helvik
Senior Installation Engineer
amund.helvik@oceaninstaller.com

Installer